Battle Green Improvements/Town Center Streetscape Project

Intersections of:

Bedford Street @ Hancock Street / Harrington Road (Presented on October 19, 2015)

Massachusetts Avenue @ Woburn Street / Winthrop Road / Fletcher Avenue

Board of Selectmen Meeting November 30, 2015





Discussion Points

- I. Massachusetts Avenue @ Woburn Street/Winthrop Road/Fletcher Street
 - 1) Address questions from previous Board meetings



Questions and Answers

1. In lieu of a traffic signal at Woburn Street, would it be feasible to add pedestrian crossing at locations such as the Police Station, bike path, Muzzey School? Cost? Visual Impact? Effectiveness? Also, should turning restrictions (eg. No left turn) be added on Winthrop?

Yes, it is feasible to add pedestrian beacon systems such as the RRFB (Rectangular Rapid Flashing Beacon) at these locations, provided a full signal system is not proposed at the Woburn Street intersection. The cost is approximately \$30K/crosswalk. For visual impact, the flashing Beacons are bright strobe lights. Solar power system is not recommended due to the visual impact. Research indicates that the RRFB is effective.

A Left Turn restriction on Winthrop Road would yield little benefit as the turn volumes are small (5 to 10 vehicles during the peak commuting hours).

2. Clarify the cost of just the traffic signal vs. the other aspects of the project.

Approximately \$150K to \$200K.

- 3. What data did BETA use that suggests that a traffic signal is called for?
- Traffic Data (Volumes and Crash) Collected in 2013, 2014 and 2015
- MUTCD Warrants
- Pedestrian and Bicycle Data
- Special Events Observations





Rectangular Rapid Flashing Beacons (RRFB)













Questions and Answers

4. What is the projected cost of the entire streetscape project?

Approximately \$8 million.

5. We are using 2008-2010 data for this study. Can DPW provide/use more current data?

Current available data was expanded to 2013, 2014 and 2015.

6. Are we examining the neighborhood impact and potential for cut thru traffic?

Yes, additional data were collected in 2014 and another consultant was hired to evaluate the potential impact.

7. Can we do a low cost test of: No left turn out of Winthrop?

Yes, however, a Left Turn restriction on Winthrop Road would yield little benefit as the turn volumes are small (5 to 10 vehicles during the peak commuting hours).

8. Can we test a no right turn lane on Mass Ave at Waltham St. to see the impact on eastbound traffic?

Yes, the test would consist of coning off the existing right-turn lane, counting traffic and observing the queuing on Mass Ave eastbound. The traffic signal head display and timing would be adjusted too.





Questions and Answers

9. Can the Battle Green portion of this study be brought up to the same level of design as the rest of the project?

The Battle Green Project can be advanced and direction on the Harrington Road/Bedford Street intersection will help these efforts. If it is the desire of the Board to advance the Battle Green Project to the level of the Center Streetscape Project, we can hold the Center project and work toward advancement of the Battle Green Project until it reaches the 25% design level.

- 10. If a round-about is installed at Woburn, how close would it be to the Russell Square condos? Approximately 20 feet. The current offset ranges between 45' and 75'
- 11. Can the Town lower the speed limit in the Center to 20-25 mph and also add speed monitoring signs? Would like a tutorial on establishing speed limits and what the 85th percentile means.

All regulatory speed limits are under MassDOT jurisdiction. Regulatory speed limits are established based on a speed study and the 85th percentile speed. The 85th percentile speed is the speed at or below which 85% of all vehicles are observed to travel under free flowing conditions.


12. How do the engineers decide where to locate crosswalks in the Center?

Crosswalks are located based on the ability to provide a safe crossing and pedestrian desire lines. A pedestrian desire line is a path that represents pedestrian's desired route between an origin point and a destination point. A good example is the crosswalk located on Mass Ave at Meriam Street.

BETA ENGINEERING SUCCESS TO GETHER

Massachusetts Avenue / Woburn Street / Winthrop Road

Option 6 - Intersection With Roundabout




GINEERING SUCCESS TOGETHER

Lexington Town Center Streetscape Project

October 19, 2015 Page 7

Crosswalk at Meriam Street







Questions and Answers

13. Is it possible to get a waiver on the speed limit setting requirements?

No! The Town is liable for any non-conformance design regulations.

14. Can we move the MBTA bus stop at Winthrop to closer to the Baptist church?

MBTA bus stop locations are under the MBTA jurisdiction. Bus stop locations are based on ridership demand at the desire location and the spacing between stops. The locations shown in the plan were derived based on meetings with users.

15. Should we put the utilities underground as part of this project? What would be the cost?

The estimated cost for undergrounding the 11 poles from Lexx Restaurant to the Woburn Street intersection (1,000 ft) is approximately \$2 million.

16. What does prep for signals without the actual final install entail? Can this be done with the proposed geometry?

The traffic signal underground electrical conduits and cable pull boxes can be installed with the proposed geometry. The remaining traffic signal equipment could be installed at a later date. The proposed geometry without a traffic signal would create significant delays and queues on Woburn Street. A graphic display of the impact is shown in an upcoming slide.





Questions and Answers

17. Have we looked at the types of accident date (ie. Rear end vs side swipe, etc...)

Yes! A detailed analysis of accident data was performed.

18. What is the wait time versus the queue under the different scenarios?

A summary of the delay times and queue lengths is provided on the next two slides.

19. Has a CO reduction calculation been done for the signals? If not, can it be done?


No, a CO analysis was not performed. CO can be calculated. The estimated cost to complete a CO analysis is approximate \$10K. The CO reduction could be minimal based on the traffic analysis results between the existing and proposed signal conditions.



Page 10

Massachusetts Avenue / Woburn Street/Winthrop Road/Fletcher Avenue

Delay Times and Vehicle Queues – AM Peak Hour




B E T A



Massachusetts Avenue / Woburn Street/Winthrop Road/Fletcher Avenue

Delay Times and Vehicle Queues – PM Peak Hour







Thank You!



